

BODEWES ECO TRADER 8250 TDW/GEARED



Main particulars

Length over all	119.05	m.
Length b.p.p.	116.95	m.
Breath mld.	15.80	m.
Depth mld.	10.05	m.
Design draught	6.95	m.
Dead weight	8250	mtons
Tonnage	5568	GT
Speed	13.5	knots

General cargo capacities

Grain capacity	380500	cft
Tank top load	15	ton/m ²
Depth of cargo hold	10.20	m.
Width of cargo hold	13.25	m.
Tank top area	1039	m ²

Container capacities (TEU)

In hold	177
On deck	110
Total	287
14 ton v.c.g. 45%	287

Tank capacities

Gas oil	78	m ³
IFO 180 or 380	537	m ³
Potable water	71	m ³
Ballast water	3337	m ³

Navigation equipment

Com. and nav. equip. acc. to GMDSS area A3

Classification

Lloyd's Register of Shipping: 100A1 Strengthened for heavy cargoes.
Equipped for carriage of containers. UMS, LMC, with descriptive note SCM
Equipped for carriage of dangerous goods. Unrestricted area.

Propulsion

Main engine:	MaK: 6M32
Output:	2999 kW
Gearbox:	Renk
C.P.P.:	Berg
Rudder:	Rolls Royce /Benes

Equipment

3 x Diesel generator sets 265 kW
1 x Shaft generator 452 kW
1 x Emergency gen. 96 kW
Bowthruster 300 kW

Accommodation

For a crew of 12 persons, each person has a single berth cabin.
Complete accommodation with ventilation, heating and air-conditioning.

Hatches, Tweendeck/Separation bulkheads

Cargo holds are provided with pontoon hatch covers. Cargo holds are equipped with in total 15 tweendeck panels, eight panels can be used for four separation bulkhead.

Deck cranes

The ship will be equipped with 2 NMF deck cranes, type DK II 40025-50.
SWL: 60/40/34 tonnes, 16/25/28 m
Outreach: 3.0-16m / 3.0-28.0m
Weight: 47.5 tonnes each

* = tweendeck panels not on board



www.bodewes.eu
+31(0)598 393131
info@bodewesshipyards.nl

